

1-1-27W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. G. HANSEN
Farm- Sater

No. 4

SEC. 1 T. 1 R. 27W
NW SW SW

Total Depth. 3460'

Comm. 12-1-56


Comp. 12-10-56

Shot or Treated.

Contractor.

Issued. 5-25-57

County Decatur
KANSAS



CASING:

8 5/8" 304'

5 1/2" 3466'

Elevation. 2566' DF

Production. 40 BOPD

All Meas. fr RB

Figures indicate Bottom of Formations.

shale	780
shale-sand	1400
lime-shale	1660
lime-red bed	1934
Anhydrite	1965
lime-shale	2615
lime	2770
lime-shale	3460
Total Depth	

TOPS: Geol.

Anhydrite	1936
Severy Sand	3048
Topeka	3063
Heebner	3194
Toronto	3215
Lansing	3232
B/Kansas City	3447
Penn. Sand	3451

DST #4 - 3347-75 Weak clog through
test. Open 1 1/2 hrs. Rec. 10' oil
& 30' HOCM & 585# BHP.

DST #5 - 3386-3405 Weak blow for
17 min. Rec. 14' OCM & 1' oil &
45# BHP.

DST #6 - 3411-40 Weak blow for
7 min. Rec. 7' very slightly OCM
& 0# BHP

DST #1 - 3233-58 Open 1 hr.
w/weak blow fro 15 min., Rec.
3' oil & 17' HOCM w/325# BHP
after 24 min. & still climbing.

DST #7 - 3444-60 Weak blow for 11
min. Rec. 6' oil & 22' OCM & 105#
BHP.

DST #2 - 3273-3304. Weak blow for
2 min. Open 45 min. Rec. 8'
slightly OCM & 65# BHP.

DST #3 - 3316-40 Weak blow for 7
min. Rec. 12' mud & few spots
oil & 75# BHP.