

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2-1-276

Company- JOE ROTHMEIR, SAUVAGE & DUNN DRLG CO.
Farm- Kilzer No. 1

SEC. 2 T. 1 R. 27W
SE SE NE

Total Depth. 3500
Comm. 8-14-56 Comp. 8-23-56
Shot or Treated.
Contractor. Sauvage & Dunn Drlg. Co., Inc.
Issued. 3-16-57

County Decatur
KANSAS



CASING:
8" 286'
5" 3500'

Elevation. 2590 R.B.

Production. Phy. Pot. 57 BOPD

Figures indicate Bottom of Formations.

cellar	5
shale	75'
sand, shale	900
shale, shells	1834
red bed	1957 ✓
anhydrite	1980 ✓
red bed, shale	2048 ✓
shale, shells	2141 ✓
lime, shale	3304 ✓
lime	3336 ✓
lime, shale	3476 ✓
lime	3500 ✓
Total Depth	

Tops: Scout.
Anhydrite 1957
Topake 3127
Lansing 3280
Base Kansas City 3485

- 8-28-56 Rigged up - strung up tools
Swabbed hole dry. Drld 76 ft.
of cement, 1 plug. Took Electric
log.
- 8-29-56 Swabbing hole. Swabbed 80 bbls
Bailed off bottom. Cleaned up
bottom hole. Fluid Approx. 2500
ft. in hole. Swabbed within
600 ft. of bottom.
- 8-30-56 Checked fluid level, found fluid
@ 1210. Bailed off bottom--
no water. Run tubing.
- 8-31-56 Testing for fluid approx. 1500
ft. of fluid in hole. Strung up
tubing swab. Swabbing thru tbg.
- 9-1-56 Swabbing & testing Thru 2" tubing.
- 9-2-56 Swabbing & testing. Well swabbed
8652 bbls. in 10 hrs.
- 9-3-56 Checked fluid level -- 770 ft.
fluid in hole. Hole filled up
230 ft. over night. Run rods -
hung pump. Pumped well -- pumped
up at 6:00 o'clock.
Tore Down.

Drill Stem Tests:

- #1 3281-3304/1 hr, 80' HOCM, BHP 675#.
- #2 3385-3410/1½ hrs. 10' mud, BHP 890#.
- #3 3461-72/1 hr., 2050' gassy oil, BHP 1150#.

Perf. 44/3465-72, 2200' OIH/1½ hrs.