

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

2-1-27W


W. W. SAUVAGE &
Company- JOE ROTHMEIER
Farm- Kilzer No. 1

SEC. 2 T. 1 R. 27W
SE SE NE

Total Depth. 3500' RTD
Comm. 8-15-56 Comp. 1-25-57
Shot or Treated.

County Decatur
KANSAS

Contractor. Sauvage & Dunn Drilling Company
Issued. 4-20-57



CASING:

Elevation. 2587' G.L.

8" 286'
5" 3500'

Production. 57 BOPD

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

FORMATION TOPS

Anhydrite(Drillers) 1957
Topeka 3127
Lansing/Kansas City 3280

DST #3 Interval: 3434-3454'
Op. 30 min. w/weak blow for
8 min. Packer failed when
tool was flushed. Rec. 175'
of mud. SIP none recorded.
DST #4 Interval: 3461-3476'
Op. 1 hr. w/strong blow
thr-out. Rec. 2050' of free
oil. IFP 560#, FFP 725#,
SIP 1150# in 20 min.

SAMPLE DESCRIPTION:

Topeka Lime 3230-3240
chalky lime w/occasional
dark oil stain & slight
porosity. not considered
worthy of testing.
Lansing/Kansas City
3280-3286' Fossiliferous
white lime w/occasional
stain & slight porosity.
wet samples held occasional
free oil. This show
was open on #1 drill
stem test.
3292-3297 limy & silty
sand w/occasional stain
& slight porosity. wet
samples had occasional
free oil. show was open
on #1 drill stem test.
3366-71' lime w/rare
stain & slight -fair
vugular porosity.
3395-3405 lime w/rare
stain & poor pin-point
proosity.
3435-3440 lime w/
occasional stain & slight
pin-point porosity.
3460-3474 lime w/
spotty stain & good
vugular porosity. wet
samples had abundant
free oil but no odor.

DRILL STEM TESTS

DST #1 Interval 3281-3304
Op. 1 hr. w/fair blow
thr-out. Rec. 150' of
gas & 82' of oil cut mud.
IFP 0#, FFP 0#, SIP 675#
in 20 min.
DST #2 Interval: 3385-3410
Op. 30 min. w/weak blow
for 12 min. Rec. 10' of mud
w/few specks of oil
SIP-890# in 20 min. FP 0#.