

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2-1-27W

Company- CITIES SERVICE OIL
Farm- Sater No. 3
" Warner unit 103"

SEC. 2 T. 1 R. 27W
NE NE SE
330' S 330' W of E $\frac{1}{4}$ Cor.

Total Depth. 3618' PB 3588'
Comm. 9-10-56 Comp. 9-19-56
Shot or Treated.
Contractor. Lohmann-Johnson Drlg. Co., Inc.
Issued. 12-1-56

County Decatur
KANSAS



Elevation. 2586' DE

CASING:
8 5/8" 318' w/250 sx cem.
5 1/2" 3618' w/200 sx cem.
DV-tool 1990' w/400 sx cem. & 225' cu. ft. Strataprete
Figures indicate Bottom of Formations.

Production. 76 BO - 19 wtr. 24 hrs.

shale	375 ✓
shale-sand	1365 ✓
shale	1965 ✓
anhydrite	1990 ✓
shale-lime	2180 ✓
lime-shale	2705 ✓
lime	3139 ✓
shale	3203 ✓
lime-shale	3280 ✓
lime	3495 ✓
cored shale-lime	3501
lime	3620
3620 = 3618 SIM	

TOPS:
Corr. Howard 3003
Corr. Topeka 3105
Corr. Heebner 3228
Corr. Dodge 3250
Corr. Lansing 3266
Corr. B/Kansas City 3480
Corr. Penn. sand 3483
Corr. Granite Wash 3600
Penetration 18'
Corr. Total Depth 3618
Drilled cem. to 3588' SIM

Perf. 33 shots 3483-91
251' fluid in 1 hr. 20 min.
402' " " 2 hrs. 20 min.