


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

9-1-27W

Company- CITIES SERVICE OIL COMPANY
 Farm- Hendricks No. 1

SEC. 9 T. 1 R. 27W
 SW SW NE
 330' E ; 330' N CL
 County Decatur
 KANSAS

Total Depth. 3642
 Comm. 9-12-57 Comp. 9-21-57
 Shot or Treated.
 Contractor. Lohmann-Johnson Drilling Co., Inc.
 Issued. 11-2-57



CASING:

8 5/8" 320' cem w/250 sx

Elevation. 2567

Production. Dry

Figures indicate Bottom of Formations.

Sand & Shale	1220
Lime & Shale	1539
Shale	1965
ANhydrite	2005
Lime & Shale	2110
Shale	2410
Shale & Lime	2555
Lime	3595
Lime & Sand	3616
Lime	3642
Total Depth	

TOPS:

Howard	3009
Topeka	3113
Lansing	3272
Base Kansas City	3489
Reagan	3612
Granite Wash	3624
Granite	3637
Pen.	5

DST 3273-95, open 30 min. rec. 8' mud; BHP 80# in 30 min.
 DST 3316-70, open 1 hr. rec 37' mud with scum oil; SHP 775# in 30 min.
 DST 3425-70, open 1 hr. rec 10' mud; BHP 40# in 30 min.
 DST 3602-16, open 1 hr. rec 735' salt water; BHP 935# in 30 min.

7 7/8" Rotary Hole