

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

9-1-27W


Company- CITIES SERVICE OIL
Farm- Van Vleet No. 1

SEC. 9 T. 1 R.27W
NW NE NW
330' S 1650' E NW cor.

Total Depth. 3608' PB 3550'
Comm. 5-4-56 Comp. 5-12-56

County Decatur
KANSAS

Shot or Treated.
Contractor. Lohmann-Johnson Drlg. Co., Inc.
Issued. 7-14-56



Elevation. 2559(2557 Gr.)

Production. Phy. Pot. 31 oil,
31 wtr. 24 hrs.

Figures Indicate Bottom of Formations.

CASING:
8 5/8" 320' w/250 sx cem.
5 1/2" 3608' w/175 sx cem.

shale-sand	320
shale-sand-shells	1947
anhydrite	1987
shale-lime	2994
lime	3115
lime-shale	3260
lime	3495
shale-lime	3574
lime-granote	3611
3611 = 3608 SLM	
Total Depth PB 3550	

TOPS:

Corr. Anhydrite	1944
Corr. Howard	2968
" Topeka	3080
" Heebner	3195
" Lansing	3238
" B/Kansas City	3452
" Reagan	3567
" Granite Wash	3591
" Granite	3605
Penetration	3'

Perf. 44 shots 3423-34

5-18-56 Acidized 500 gals.
5-19-56 Acidized 1000 gals.
5-22-56 Pumped 12 oil, 3.5
wtr., 24 hrs.

Perf. 33 shots 3356-65, no fluid.
Perf. 6 " 3333-39, no fluid.
" 33 " 3321-30, 2 gals.
wtr. in 20 mins.
" 15 shots 3277-92.
" 33 " 3235-44.

5-24-56 Acidized 500 & 1000 gals.
3235-55.
5-25-56 Pumped 7 oil, 20 wtr.,

24 hrs. zone 3235-44.
5-26-56 Acidized 500 & 1000 gals.
3356-65.
5-28-56 Pumped 13 oil, 23 wtr. 24
hrs. zones 3235-44 & 3356-65.