

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


11-1-27W
15-039-00106

Company- CITIES SERVICE OIL CO.
Farm- Warner "E" No. 1

SEC. 11 T. 1 R. 27W
NE NE SW
330' S & 330' W of Center

Total Depth. 3529' PB 3333' SLM
Comm. 4-5-56 Comp. 4-14-56
Shot or Treated.
Contractor. Lohmann-Johnson Drlg. Co.
Issued. 6-9-56

County Decatur
KANSAS



CASING:

8 5/8" 320' cem w/250 sx
5 1/2" 3529' cem w/200 sx

Elevation. 2185'

Production. 330 BO, 30% wtr,
24 hrs.

Figures indicate Bottom of Formations.

sand & shale	320
shale & sand	1100
sand & shale	1570
shale & red bed	1841
anhydrite	1870
shale & lime	2190
lime & shale	2347
shale & lime	2778
lime	3050
lime & shale	3126
lime	3248
lime & shale	3305
lime	3530

3530 RTD = 3529 SLM

Total Depth
Plug back to 3333' SLM

Tops: Corr.	
Howard	2870
Topeka	2988
Heebner	3104
Dodge	3130
Lansing	3146
Reagan	3470
Granite Wash	3473
Penetration	56'

Drilled cement to 3484 SLM
Perf. 58 shots 3324-41'.
2160' fluid in 12 mins.
2833' fluid in 1 1/2 hrs.