

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-039-06529


11-1-27W

Company- CITIES SERVICE OIL CO.  
Farm- Warner "E" No. 2

SEC. 11 T. 1 R.27W  
NE NW SE  
330' S & 990' E of center

Total Depth. 3429 SLM PB 3355 SLM  
Comm. 8-20-56 Comp. 8-27-56  
Shot or Treated.  
Contractor. Lohmann-Johnson Drlg Co., Inc.  
Issued. 10-27-56

County Decatur  
KANSAS



Elevation. 2535 DF

CASING:

8 5/8" 316' cem w/250 sx.  
5 1/2" 3429' cem w/200 sx.

Production. Phy. pot. 324 Oil /  
5% water, 24 hrs.

DV-tool @ 1913' cem w/400 sx. Figures indicate Bottom of Formations.

sand, shale 316  
shale 825  
shale, sand 1675  
shale 1898  
anhydrite 1922  
shale 2005  
shale, lime 3030  
lime 3430

3430 RTD = 3429 SLM

Total Depth

Plugged Back to 3355 SLM

Tops: Corr.

Howard 2933  
Severy sand 3016  
Topeka 3041  
Heebner 3161  
Dodge 3190  
Lansing 3202  
Base Kansas City 3415

Drilled cement to 3411 SLM

Perf. 21 shots 3381-86; 1086 salt wtr in 1 hr. 10 mins.

Set Lans-Wells plug at 3366; 4 gals. rock  
plug; PBTB 3362 SLM

Perf. 33 shots 3323-31

" 17 " 3315-19  
" 17 " 3253-57  
" 41 " 3241-51  
" 21 " 3233-38  
" 41 " 3202-12

Dumped 1 sack Calseal on plug;  
PBTB 3355 SLM

9-7-56 Az. 1500 gals 3315-31  
9-8-56 Az. 2000 " 3233-57  
9-9-56 Az. 1000 " 3202-12