

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas

15-039-19003


11-1-27W

Company- D. G. HANSEN  
Farm- Redman No. 1

SEC. 11 T. 1 R. 27W  
SE SE NW

Total Depth. 3400'  
Comm. 2-18-57 Comp. 2-27-57  
Shot or Treated.  
Contractor.  
Issued. 6-1-57

County Decatur  
KANSAS



Elevation. 2502' RB

CASING:

8 5/8" @280' surface casing  
5 1/2" @3389'

Production. 38 BOPD (Physical  
Potential)

Figures indicate Bottom of Formations.

(All Measurements taken from the top of Rotary Bushing)

shale	800
shale, sand	1365
shale, shells	1680
shale	1861
Anhydrite	1885
lime, shale	3400 RTD
Total Depth	

TOPS	
Anhydrite	1861 ✓
Topeka	2992
Severy	2972
Heebner	3118
Lansing	3160
Base/Kansas City	3372
Sand	3377-82'

DRILL STEM TESTS

DST #1 3163-85' Op. 41 min.  
Wk. blow 10 min. 35' mud &  
few oil specks. 890#.  
DST #2 3170-3225' op. 1½ hrs.  
mod. strong blow & decreased  
to mod. blow. Rec. 45' gas,  
20' oil & 175' VHOOM. Had 90#  
FFP but BHP did not register.  
Are sure the BHP was about  
same as off setting wells-  
in neighborhood of 1000#.  
DST #3 3219-65' op. 1 hr.  
wk. blow 20" & very weak  
thru test. Rec. 50' mud  
& trace oil 770# BHP.  
DST #4 3326-57' op. 1 hr.  
Very strong blow to start  
& by end of hour had  
stopped. Rec. 500' MSW  
& spots oil in 1st stand.  
210# FFP & 210# BHP & FFP  
of 90#.