

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-039-00534


11-1-27W

Company- D. G. HANSEN  
Farm- Redman No. 2

SEC. 11 T. 1 R. 27W  
C E/2 E/2 NW

Total Depth. 3400'  
Comm. 3-11-57 Comp. 3-19-57  
Shot or Treated.  
Contractor.  
Issued. 6-1-57

County Decatur  
KANSAS



Elevation. 2499' RB

Production. 38 BOPD (Physical  
Potential)

Figures indicate Bottom of Formations.

(All measurements taken from the top of Rotary Bushing.)

|                |          |
|----------------|----------|
| surface soil   | 256      |
| shale, sand    | 910      |
| sand, shale    | 1480     |
| shale, red bed | 1855     |
| Anhydrite      | 1890     |
| shale          | 1895     |
| lime, shale    | 3400 RTD |
| Total Depth    |          |

|                   |      |
|-------------------|------|
| TOPS              |      |
| Anhydrite (Scout) | 1855 |
| Howard "          | 2897 |
| Severy Sand       | 2976 |
| Topeka (Scout)    | 3002 |
| Heebner           | 3121 |
| Toronto           | 3145 |
| Lansing           | 3160 |
| Base/Kansas City  | 3377 |

DRILL STEM TEST

DST #1 3162-88' op. 1 hr.  
wk. blow thru test. Rec.  
15' MCO, 30' OCM & 930#  
BHP.

DST #2 3193-3225' op. 1/2 hr.  
wk. blow. 3 min. Rec. 20'  
mud. 120# BHP

DST #3 3218-65' op. 1/2 hr.  
wk blow 3 min. Rec. 15' mud  
& 540# BHP.

DST #4 3267-3300' op. 1 hr.  
wk. blow 3 min. Rec. 15'  
mud & 90# BHP.

DST #5 3295-3330' op. 30"  
wk. blow 5 min. Rec. 25'  
mud & tr. of oil & 770#  
BHP.

DST #6 3327-60' op. 50 min.  
wk. blow 20" Rec. 5'  
mud 70# BHP.

DST #7 3367-3400' wk. blow  
3" 10' mud & 60# BHP.