

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-039-00522
11-1-27W

Company. CITIES SERVICE OIL CO.
Farm. Sater No. 1

SEC. 11 T. 1 R. 27W
SW SW NE
330' N & 330' E of Center

County Decatur
KANSAS

Total Depth. 3418 PBD 3402
Comm. 7-21-56 Comp. 7-29-56
Shot or Treated.
Contractor. Lohmann-Jonson Drilling Co., Inc.
Issued. 9-15-56



Elevation. 2531 DF

Production. 497 BO, 26 BWPD

CASING:

8 5/8 @ 320' w/ 250 sx cmt.
5 1/2 @ 3418' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

shale	460
shale & sand	1490
shale & lime	1874
shale	1888
anhydrite	1913
shale & shells	2550
shale & lime	3150
lime	3160
shale & lime	3253
lime	3400
lime & shale	3420
SLM	3418
Total Depth	

Plugged back to 3402

TOPS: (Corrected)

Howard	2921
Topeka	3025
Heebner	3148
Dodge	3172
Lansing	3186
Base KC	3400

Perf. 33/3306-14, 1000 gals acid
Pmpd. 176 BO, 33 BW/24 hrs.
Perf. 37/3227-36, 1000 gal acid
Pmpd. 154 BO, 8 BW/14 hrs.
Perf. 41/3186-96, 1000 gals. acid
Pmpd. 183 BO, 23 BW/19 hrs.

778' oil, 92' water/13 hrs.