

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-039-00523


11-1-27W

Company- CITIES SERVICE OIL CO.
Farm- Sater No. 2

SEC. 11 T. 1 R. 27W
NE SW NE
990' N, 990' E of center

Total Depth. 3436 SLM PB 3417
Comm. 8-11-56 Comp. 8-18-56
Shot or Treated.
Contractor. Lohmann-Johnson Drig Co., Inc.
Issued. 10-27-56

County Decatur
KANSAS



CASING:

8 5/8" 320' cem w/250 sx.
5 1/2" 3436' cem w/200 sx.
DV-tool at 1932' w/400 sx.

Elevation. 2554 DF

Production. Phy. Pot. 301 oil,
2% wtr.

Figures Indicate Bottom of Formations.

sand, shale	320
shale	450
sand, shale	1535
shells, shale	1916
anhydrite	1938
shale	1988
shale, shells	2405
shale, lime	2738
lime	2791
shale	2910
shale, lime	3028
lime	3130
shale, lime	3225
lime	3275
lime, shale	3350
lime	3440

3440=RTD - 3436 SLM

Total Depth PB 3417

Tops: Corr.
Howard 2940
Topeka 3043
Heebner 3169
Dodge 3191
Lansing 3207
Base Kansas City 3423

Drilled cement to 3417 SLM

Perf. 24 § 3387-93
" 33 § 3330-38
" 21 § 3322-27
" 21 § 3259-64
" 37 § 3248-57
" 17 § 3240-44
" 45 § 3207-18

205' oil in 55 mins.

457' oil in 1 hr. 55 mins.

780' oil in 3 hrs. 25 mins.

1863' oil & 9' wtr in 18 hrs. 15 mins.

8-24-56 Az. 500 gals. 3387-93
8-25-56 Az. 3500 " 3240-3338
8-27-56 Az. 1000 " 3207-18