

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

15-065-00526
11-1-27W

Company. CITIES SERVICE OIL COMPANY
Farm. Sater No. 6

SEC. 11 T. 1 R. 27W
NE NE NE
330' S & 330' W of
NE Corner
County Decatur KANSAS *Warner*

Total Depth. 3450' PBD 3434'
Comm. 10-25-56 Comp. 11-3-56
Shot or Treated.
Contractor. Lohmann-Johnson Drilling Co., Inc.
Issued. 12-8-56

CASING:

8 5/8" @320' 250 sx cem.
5 1/2" @3451' w/200 sx cem.

Elevation. 2563' DF

Production. Physical Potential
225 oil, 1% water, 24 hrs.

Figures indicate Bottom of Formations.

DV-tool at 1953' w/400 sx
cem. & 225 cu ft. Stratacrete

shale & sand	320
shale	450
shale, sand & shells	1270
shale	1926
Anhydrite	1953
shale	2110
shale & lime	2675
lime	2824
shale & lime strks	2948
lime	3058
lime & shale	3240
lime	3450 RTD

Total Depth
SLM 3452

TOPS; Corr.
Howard 2955
Severy 3032
Topeka 3053
Heebner 3178
Dodge 3200
Lansing 3216
Base/Kansas City 3430
Pennsylvanian Sand 3434

Drilled cem. to 3434' SLM

PERFORATING RECORD:

21 sh. 3338-43
24 sh. 3312-18
37 sh. 3298-3307
21 sh. 3269-74
41 sh. 3254-64
45 sh. 3216-27

Acidizing Record 11-9-56
500 gals. 3338-43
1500 gals. 3298-3318
2500 gals 3216-74

7 7/8" rotary hole