

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


15-039-00527
11-1-27W

Company- CITIES SERVICE OIL CO.
Farm- Sater No. 8

SEC. 11 T. 1 R. 27W
SW SE NE
330' N 990' W of E $\frac{1}{4}$ Cor.

County Decatur
KANSAS

Total Depth. 3452' SIM PB 3435'
Comm. 7-20-57 Crisp. 7-29-57
Lohmann-Johnson Drlg. Co., Inc.
9-28-57



CASING:
8 5/8" 320' w/250 sx cem.
5 1/2" 3451' w-200 sx cem.
DV tool @ 1939' w/400 sx cem.

Elevation. 2551

Production. Phy. Pot. 60 oil,
3% wtr. PD

Figures indicate Bottom of Formations.

sand-shale	320
shale-sand-shells	1000
shale-sand	1340
shale	1915
anhydrite	1942
shale	2005
lime-shale	2411
lime	3455

3455 RTD. = 3452 SIM
Total Depth PB 3435'

TOPS:
Corr. Topeka 3062
" Lansing 3219
" B/Kansas City 3434

Drilled cement to 3435 S.L.M.

Perf. Record:

35 shots 3300-3309
20 " 3260-65
23 " 3250-56
41 " 3218-28

Acidizing Record 8-6-57

1000 gals. 3300-3309
1250 " 3250-65
1000 " 3218-28