

MAR 27 1971

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

ELEVATION:
SURFACE CASING:
OIL STRING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

Donald C. Slawson
Aspen Drilling Co.
Wicke 'C' #1

C NW-SW Sec. 17-T1S-R32W
Rawlins County, Kansas
2924 K. B.
17 jts. (351') 8 5/8"
128 jts. (4154') 4 1/2"
November 2, 1970
November 12, 1970
4140'

<u>FORMATION</u>	<u>DEPTH</u>
Sand & Shale	358
Shale & Shells	2250
Shale & Lime	2709
Anhydrite	2748
Shale & Lime	3110
Lime & Shale	3870
Lime	3915
Lime & Shale	3944
Lime	4090
Lime & Shale	4140
RTD	4140

Ran 17 jts (351') 8 5/8" casing set
at 358' with 250 sacks 60/40 Pozmix.
Cement circulated.

DST #1 3857-3915
DST #2 3910-3945
DST #3 3988-4045
DST #4 4045-4090

Sample Logs
anhydrite 2709
B. " 2748
Jopoka 3694
Dread 3793
Heckner 3807
YKC 3844
BKC 4113

Ran electric log.

Ran 128 jts. (4154') 4 1/2" casing
set at 4139' w/150 sacks.

Log Logs
YKC 3848
BKC 4116

AFFIDAVIT

State of Kansas)
) ss:
County of Barton .)

The undersigned, being duly sworn on oath, states that the above
statement and log are a true and correct record and log of the well drilled at
the location above described.

William S. Schachle
William S. Schachle, Affiant

Subscribed and sworn to before me this 16th day of November, 1970.

Theora Holleman
Theora Holleman, Notary Public

My commission expires: April 18, 1972.