

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


30-1-32W

Company- SAM G. HARRISON
Farm- Simminger No. 2

SEC. 30 T. 1 R. 32W
C NE NW
600' FNL, 720' FEL NW/4

Total Depth. 4270'
Comm. 6-5-64 Comp. 6-12-64
Shot or Treated.
Contractor. Empire Drlg. Co.
Issued. 1-2-65

County Rawlins
KANSAS



Elevation. 3040' G.L.

Production. Pump 2 BOPB, NW

CASING:

8 5/8" 301' w/200 sx cem.
5 1/2" 4269'

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: ELEC.

Stone Corral	2834
Topeka	3825
Oread	3934
Douglas sand	3960
Lansing-Kansas City	3980
T.D. Schl	4250
T.D.. Drlr.	4270

DST # 1 - 4080'-4108' OCM 230',
Weak blow increasing to medium
blow in - 40 mins. ISI 30", FP
1 hr., FSI 46", Pres. IHM 2126#,
ISI 1232#/ IF 34#; FF 89#; FSI
1079#; FHM 2109#.

DST #2 - 4170-4210' Rec 50'
OCM; 120' MCO; Weak blow increas-
ing to good medium blow through-
out test. ISI 30"; FP 1 hr.; FSI
45"; IHMP 2160#; ISIP 1186#; IFP
23#; FFP 63#; FSIP 1053#; FHMP 2126#.

DST # 3 - 4077-4117' Rec. OCM 62';
Blow weak for 12 : & died dead throu-
ghout test. ISI 30"; F) 1 hr.; FSI
51"; SHMP 2116#; ISIP 165#; IFP 34#;
FFP 34#; FSIP 183#; FHMP 2107#

Electric log was run.