

not

5-1-33 W.

James Douglas Swamy

WICHITA BRANCH

CONTRACTORS WELL LOG

SEP

OPERATOR: Petroleum Management, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: PALMER 'B' #3
 LOCATION: C S/2 S/2 SW, Sec. 5-1S-33W
 Rawlins County, Kansas
 SPUD DATE: 10/10/81
 COMPLETION DATE: 10/15/81

0	180	Clay & Sand
180	1293	Shale
1293	2855	Shale & Sand
2855	2895	Anhydrite
2895	3245	Shale
3245	3450	Shale & Lime
3450	3635	Shale
3635	3824	Lime & Shale
3824	3850	Shale & Lime
3850	3967	Lime
3967	4200	Lime & Shale
	4200	Rotary Total Depth

Spud hole @ 11:45 a.m., 10/10/81. Drilled 270' of a 12 1/2" hole. Ran 6 jts. of 8 5/8" 28# casing set @ 266' and cemented with 190 sx. 60-40 posmix, 3% c.c., 2% gel. Cement did circulate Plug was down @ 3:30 p.m., 10/10/81.

4200' TD. Ran 105 jts. 4 1/2" 10 1/2# casing set @ 4197' and cemented with 100 sx. Halliburton Lite followed by 150 sx. 60-40 posmix, 10% Salt, 2% gel, .75% CFR-2. Plug was down @ 2:30 p.m., 10/15/81.

SAMPLE TOPS:

Anhydrite 2855'
 B/Anhydrite 2895'

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 21 1981
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the PALMER 'B' #3, C S/2 S/2 SW, Sec. 5-1S-33W, Rawlins County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 21st day of October, 1981.