

IND

29-1-33W

# WELL LOG

A

COMPANY First Energy Corporation  
 16701 Greenspoint Park Drive, Suite 200  
 Houston, TX 77060

FARM WORLEY NO. 41(40)-29


SEC. 29 T. 1S R. 33W  
 LOC. C NE NE

RIG. NO. 24  
 TOTAL DEPTH 4681'  
 COMM. 10-11-84 COMP. 10-18-84

CONTRACTOR MURFIN DRILLING COMPANY  
 250 N. Water, Suite 300  
 Wichita, Kansas 67202

*Released*

COUNTY Rawlins  
 KANSAS



CASING

10  
 15 8-5/8" csg set @261' w/225 sx. 60-40 Poz., ELEVATION  
 12 6 2% Gel, 3% CC  
 13 5-1/2" csg set @4679' w/60 sx. 60-50/50 Pozmix, PRODUCTION  
 plus 180 sx. Common D-29, 2% Gel

FIGURES INDICATE BOTTOM OF FORMATIONS

|                    |       |
|--------------------|-------|
| Sand & Clay        | 175'  |
| Shale              | 1065' |
| Sand & Shale       | 2838' |
| Anhydrite          | 2877' |
| Shale & Shells     | 3445' |
| Shale & Lime (RTD) | 4681' |

RECEIVED  
 NOV 12 1984  
 FIRST ENERGY CORP.

MAY 30 1985

KANSAS GEOLOGICAL SURVEY  
 WICHITA BRANCH

RECEIVED  
 STATE GEOLOGICAL COMMISSION