

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-1-34W

Company- SKELLY OIL
Farm- C. G. Kisling No. 5

SEC. 10 T. 1 R. 34W
C SW SW (C SW SE) TC.
660 WL 660 SL SW/4

Total Depth. 4309'
Comm. 4-11-64 Comp. 5-6-64
Shot or Treated. Acid 4174-4178' 500 gals. 4128-4132' 500 gals.
Contractor. Muzfin Drig.
Issued. 8-15-64

County Rawlins
KANSAS



CASING:

8 5/8" 328' cem w/ 250 sx
5 1/2" 4309' cem w/ 150 sx

Elevation. 3086' KB

Production. 17.98 BOFD 17.98
BWPD

Figures Indicate Bottom of Formations.

clay & sand	200
shale	331
shale	1770
sandy shale	2100
shale & sand	2665
shale & gyp	2740
red bed	2925
Stone Corral	2940
anhydrite	2956
shale & shells	3210
shale & lime	3620
lime	3844
lime & shale	3922
lime	3975
limestone poor show	3985
lime	3998
sandstone tr free oil	4005
lime	4030
limestone poor show	4045
lime	4078
limestone tr free oil	4085
lime	4128
limestone show free oil	4134
lime	4168
limestone show free oil	4178
lime	4213
limestone poor show	4220
lime	4280
Total Depth	

PBTD 4294'

TOPS: LOG	
Fort Hzyes	1432
Permian	2670
Stone Corral	2926
Admire	3606
Topeka Lime	3793
Oread	3875
Lansing lime	3975
Marmaton	4280

B/sc - 2958 (Top Card)

DST #1 4150-83' Op 1 hr. 15 min. no
blow, Rec. 40' mud, no free oil, IFF 0#
30 min., FFP 0#, IBHSIP 0# 30 min, FBHSIP
35#.