

MAY 22 1971

15-1-34W
CNE-SE

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1971
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:
ELEVATION:
SURFACE CASING:
OIL STRING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

Log Top
anhydrite 3000
B. " 3033
Red Eagle 3641
Howard 3847
Jopka 3878
Hechner 4004
Jaronto 4007
Lanning 4056
BKC 4319

Halliburton Oil Producing Co.
Aspen Drilling Co.
Fikan #2
NE SE Sec. 15-T1S-R34W
Rawlins County, Kansas
3164' K. B.
9 jts. (315') 8 5/8"
136 jts. (4327.50') 5 1/2"
January 13, 1971
January 22, 1971
4336'.

Elev. 3164' KB

*P 60 BO N/W
LKC (GR36)*

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay	50
Shale & Sand	322
Shale & Shells	2275
Shale & Lime	2804
Lime & Shale	3004
Anhydrite	3037
Shale & Lime	3475
Lime & Shale	3840
Lime	3975
Lime & Shale	4000
Lime	4098
Lime & Shale	4144
Lime	4336

Ran 9 jts. (315') 8 5/8" casing set at 322' w/225 sacks cement. Cement did circulate.

DST #1	3930-3975
DST #2	4066-4098
DST #3	4088-4144
DST #4	4136-4185
DST #5	4175-4233
DST #6	4226-4273

Ran electric log.

Ran 136 jts. (4327.50') 5 1/2" casing set at 4331' w/200 sacks and DV tool set at 3034' w/500 sacks.

AFFIDAVIT

State of KANSAS)
) ss:
County of BARTON)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record of the well drilled at the location above described.

William S. Schackle
William S. Schackle, AFFIANT

Subscribed and sworn to before me this 25th day of January, 1971.

HOLLEMAN

Wesley Holliman