

WICHITA, KANSAS
DRILLERS' WELL LOG

15-1-34W DR
CSE SW

~~Q-SE-3W Section 15-13-34W~~

Completed: July 1, 1969

OPERATOR - Halliburton Oil Producing Co.

oil

DEPTH		FORMATION
From	To	
0	70	Surface clay and sand
70	310	Sand and shale
310	1950	Shale and sand
1950	2355	Shale and shells
2355	2396	Shale and sand w/pyrite
2396	2760	Shale and shells
2760	2994	Shale and red bed
2994	3029	Anhydrite
3029	3220	Shale and shells
3220	4025	Shale and lime
4025	4337	Lime
4337	TD	

Ran 9 joints 8-5/8" casing, set @ 310'
w/225 sacks cement.



Ran 135 joints 4-1/2" casing, set @ 4335' w/300 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SW Section 15-1S-34W, Rawlins County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

[illegible]

Before me, the undersigned, a Notary Public within and for said County and State, on this 8 day of July, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

