

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

16-1-34W


Company- SKELLY OIL
Farm- Dozbaba

No. 3

SEC. 16 T. 1 R. 34W
NE E/2 NW

Total Depth. 4398'
Comm. 4-19-63 Comp. 5-4-63
Shot or Treated.
Contracted Chem & Tech Services
Issued. 7-23-65

County Rawlins
KANSAS



CASINO:

7" 345' cem w/ 225 sx
2 7/8" 4378' cem w/ 150 sx

Elevation. 3125 KB

Production. 50 BOPD 55BWPD

Figures Indicate Bottom of Formations.

clay & shale	348
shale	1380
shale & shells	2700
red bed & Gyp	2958
anhydrite	2995
shale & shells	3008
shale & lime	3842
lime	3920
lime & shale	4050
lime	4228
lime	4398
Total Depth	

PB TD 4212

TOPS: SCOUT	
Fort Hays	1476
Permian	2700
Stone Corral	2994
Admire	3654
Oread	3924
Lansing	4023
Marmaton	4330

Treated 4261-68 28 shots 500 gal acid
4218-4231 24 shots 500 gal
4218-4231 - 2000 gal
4196-4202 16 shots 200 gal
4180-4184 16 shots 250 gal
4134-4146 22 shots 250 gal

DST # L 4213-4228 (Lansing J Zone) tool
open 1 hrs, opened with weak blow died in
5 min. Rec. 5' oil & 60' slightly oil
cut mud IFP 20 #, ISIP 30 min 481#, FSIP
30 min 350 #, FFP 30#, IHP 2073#, FHP
2073#.