

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-1-34W

Company- SKELLY OIL CO.
Farm- A. S. Cahoj No. 4

SEC. 17 T. 1 R. 34W
SE SW NE
2310' fr NL, 1650' fr EL

Total Depth. 4320' PB 4287'
Comm. 11-12-59 Comp. 11-21-59
Shot or Treated.
Contractor. Claude Wentworth Drilg.
Issued. 3-12-60

County Rawlins
KANSAS



CASING:

8 3/8" 447' cem w/400 sx.
5 1/2" 4320' cem w/250 sx.

Elevation. 3111' DF

Production. 235 BOPD

Figures indicate Bottom of Formations.

sand, clay & shale	450
shale	600
shale & shells	1015
shale	1700
shale & lime	1850
sand & shale	2295
shale & pyrite	2480
shale	2750
shale & Anhydrite	2983
shale	3345
shale & lime	3600
shale	3862
shale & lime	3991
lime	4320
Total Depth	
Plugged back to 4287'	

TOPS:

Niobrara	1080
Fort Hays	1468
Carlile	1571
Greenhorn	1748
Dakota	1876
Morrison	2503
Permian	2674
Stone Corral	2931
Chase	3081
Council Grove	3318
Admire	3620
Wabaunsee	3718
Topeka	3799
Oread	3890
Leavenworth	3942
Lansing	3991
Marmaton	4290

Ran Schlumberger Survey

Perf. #1 4229-4237' 48 shots

Treatment #1 (Acid) 4229-4237', 500 gals
of Dowell M-38 acid.

Producing Formation: Lansing Top 4229' Bottom 4237'