

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-1-34W

Company- SKELLY OIL CO.
Farm- Cahoj "D" No. 2

SEC. 17 T. 1 R. 34W
SE NW SE
1650' fr SE, 1650' fr EL

Total Depth. 4352' PB 4321'
Comm. 10-27-59 Comp. 11-8-59
Shot or Treated.
Contractor. Claude Wentworth Drlg.
Issued. 3-12-60

County Rawlins
KANSAS



CASING:

8 5/8" 450' cem w/300 sx.
5 1/2" 4352' cem w/250 sx.

Elevation. 3163' DF

Production. 440 BOPD

Figures Indicate Bottom of Formations.

sand, clay & rock	450
shale & lime	1900
sand & shale	2385
lime	2585
shale	2925
shale, lime & anhydrite	3270
shale & shells	3525
shale & lime	4025
lime	4212
lime	4256
lime	4352

Total Depth
Plugged back to 4321'

TOPS:

Niobrara	1112
Fort Hays	1516
Carlile	1624
Greenhorn	1798
Dakota	1926
Morrison	2574
Permian	2734
Stone Corral	2990
Chase	3134
Council Grove	3390
Foraker	3624
Admire	3676
Wabaunsee	3771
Topeka	3854
Oread	3952
Lansing	4048
Marmaton	4344

DST #1 4200-4212', op 30 mins., very weak
blow first 5 mins., then died. Rec. 5'
drilling mud, no show of oil. IFP 0#,
FFP 0#, SIP 1255#/30 mins., HP 2150#.

DST #2 4230-4256', op 1 hr, strong blow
in 1 min. Rec. 1710' of gas and 2200'
of free oil. IFP 180#, FFP 760#, SIP
1145#/30 mins., HP 2250#.

Ran Schlumberger Survey.

Perf. #1 4284-4287' 18 shots
4288-4291' 18 shots

Treatment #1 (Acid) 4284-4291'.
with 250 gals of Dowell M-38 acid.

Producing Formation: Lansing
Top 4284' Bottom 4291'