

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


20-1-34W

Company- SKELLY OIL CO.  
Farm- H. A. Garver No. 1

SEC. 20 T. 1 R. 34W  
NW SW NW  
990' fr SL, 330' fr WL of  
NW/4

Total Depth. 4400'  
Comm. 8-1-59 Comp. 8-13-59  
Shot or Treated.  
Contractor. Sterling Drlg. Co.  
Issued. 10-17-59

County Rawlins  
KANSAS



CASING:  
8 5/8" 450' cem w/300 sx.

Elevation. 3199' DF

Production. Dry

Figures indicate Bottom of Formations.

surface soil, shale & sand	230
shale	455
shale	1450
shale & sand	2520
shale	2850
Anhydrite	2865
shale & red bed	2890
shale	3035
lime	3075
shale	3200
shale & lime	3570
lime	3645
shale & lime	4055
lime	4119
lime	4123
sand	4131
lime & sand	4140
lime & shale	4212
lime	4235
lime	4261
lime, cream to buff, finely crystalline	4267
lime	4274
lime, cream to buff, finely crystalline	4278
lime	4282
lime	4294
lime, cream, finely crystalline poor, very spotted porosity, trace of poor stain	4299
lime	4320
lime	4338
lime, lgt gry, finely crystalline	4351
lime	4392
lime & shale	4400
Total Depth	

#3 packer set @ 4250', used 32' anchor, op 2 hrs., weak blow thruout, rec. 1' of oil, 410' of salt water, IBHP 1330#/30 mins., IFP 20#, FFP 180#, FBHP 1315#/30 min

#4 packer set @ 4278', used 42' anchor, op 1 hr., weak blow dead in 4 mins., rec. 10' rotary mud, no oil. IBHP 550#/30 mins. IFP 0#, FFP 45#, FBHP 450#/30 mins.

#5 packer set @ 4322', used 30' anchor, op 1 hr., weak blow dead in 1 min. rec. 3' of rotary mud, IBHP 300#, IFP 0#, FFP 0#, FBHP 25#/30 mins.

TOPS:  
Stone Corral 3043  
Base Stone Corral 3082  
Council Grove 3460  
Topeka 3911  
Heebner Shale 4054  
Leavenworth 4058  
Lansing Lime 4107  
Base Kansas City 4368  
Marmaton 4397

Ran Schlumberger Survey

DRILL STEM TESTS: HALLIBURTON

#1 packer set @ 4105', used 35' anchor, op 1 hr, weak blow dead in 4 mins, rec. 8' of mud, no oil. IBHP 1255#/30 mins., IFP 0#, FFP 20#, FBHP 1110#/30 mins.

#2 packer set @ 4186', used 49' anchor, op 1 hr, weak blow, dead in 4 mins., rec. 5' of rotary mud, no oil. IBHP 35#/30 mins. IFP 0#, FFP 0#, FBHP 0#/30 mins.