

NOV 1 1969

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

22-1-34W

DOZBABA #1

C NW NW Section 22-1S-34W

Rawlins County, Kansas


Commenced: July 2, 1969

Completed: July 11, 1969

oil

OPERATOR - Halliburton Oil Producing Co.

DEPTH		FORMATION	REMARKS
From	To		
0	230	Surface clay, sand, shale	
230	280	Sand and shale	
280	322	Blue shale	
322	385	Shale	Ran 9 joints of 8-5/8" casing, set @ 322' w/225 sacks cement.
385	1350	Shale and sand	
1350	1840	Shale and shells	
1840	2140	Shale and sand	
2140	2767	Shale and shells	
2767	2782	Blaine Anhydrite	
2782	2954	Shale and red bed	
2954	3001	Anhydrite	
3001	3430	Shale and lime	
3430	3455	Shale	
3455	4108	Lime and shale	
4108	4310	Lime	
4310	TD		Ran 137 joints of 4-1/2" casing, set @ 4308' w/300 sacks 18% salt saturated cement.



I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW NW Section 22-1S-34W, Rawlins County, Kansas to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 14 day of July, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public