

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-1-34W

Company- SKELLY OIL COMPANY
Farm- C. G. Kisling No. 3

SEC. 4 T. 1 R. 34W
C SW SE

Total Depth. 4270' PB 4137'
Comm. 5-17-60 Comp. 6-27-60
Shot or Treated.
Contractor. Schafer Drlg. Co.
Issued. 5-5-62

County Rawlins
KANSAS



CASING:
8 5/8" 371' cem w/300 sx.
5 1/2" 4270' cem w/200 sx.

Elevation. 3059' DF

Production. 135 BOPD

clay & shale 375 Figures Indicate Bottom of Formations.
shale & sand 1380
shale & shells 1875
shale & pyrite 2465
shale, pyrite & gyp 2905
Anhydrite 2941
shale & pyrite 3275
shale & lime 4270
Total Depth
Plugged back to 4137'

TOPS:
Fort Hays 1438
Permian 2647
Stone Corral 2902
Base Stone Corral 2940
Admire 3588
Oread 3838
Lansing 3950
Marmaton 4252

Ran Schlumberger Induction-Electrical Log
& MicroLog to 4270'.