

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


8-1-34W

Company- SKELLY OIL CO.
Farm- Cahoj "A" No. 2

SEC. 8 T. 1 R. 34W
SE NE SE
1650' fr SL, 330' fr EL

Total Depth. 4341' PB 4230'
Comm. 11-16-59 Comp. 11-25-59
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 3-12-60

County Rawlins
KANSAS



CASING:

8 5/8" 455' cem w/400 sx.
5 1/2" 4341' cem w/250 sx.

Elevation. 3126' DF

Production. 194 BOPD

Figures Indicate Bottom of Formations.

sand, clay & shale	459
shale	1400
sand & shale	2770
shale & lime	2975
shale & anhydrite	2995
shale & redbed	3160
shale & lime	3370
sand, shale & lime	3545
sand & lime	3615
shale & lime	3740
lime	4341

Total Depth
Plugged back to 4230'

TOPS:

Fort Hays	1485
Permian	2712
Stone Corral	2965
Foraker	3592
Admire	3644
Wabaunsee	3738
Topeka	3814
Oread	3900
Lansing	4004
Marmaton	4306

Ran Schlumberger Survey

DST #1 4200-4212', op 1 hr., rec. 2960'
of free oil & 5' of oil cut mud, IFP 475#,
FFP 1165#, SIP 1180#/30 mins., HP 2240#.

Perf. #1 4246-4250'	24 shots
Perf. #2 4200-4202'	12 shots
4203-4207'	24 shots
4208-4212'	24 shots

Producing Formation: Lansing
Top 4200' Bottom 4212'