

Company- SKELLY OIL CO.

Farm- Cahoj "A"

No. 3

SEC. 8 T. 1 R. 34W
SE SW SE
330' FSL 1650' FEL

Total Depth. 4643'


Comm. 11-25-59

Comp. 12-12-59

Shot or Treated.

Contractor. Claude Wentworth Drlg. Co.

Issued. 5-28-60

County Rawlins
KANSAS

CASING:

10 3/4" 367' w/300 sx cem.

7" 4643' W/300 sx cem.

Elevation. 3097' DF

Production. 292.14 BO, NW

Figures Indicate Bottom of Formations.

clay, sand, surface	371
shale	525
shale, shells	1910
shale, pyrite, sand	2491
shale	2650
shale, shells	2850
shale	2927
anhydrite	2961
shale	3502
lime, shale	4455
lime	4643
Total Depth	

TOPS:

Fort Hays	1450
Permian	2672
Stone Corral	2927
Admire	3606
Topeka	3780
Heebner	3922
Leavenworth	3926
Lansing	3974
Marmaton	4272
Cherokee	4404
Cherokee sand	4494
Cherty conglomerate	4584
Mississippian	4608
Pre-Cambrian Quartzite	4637

PERF: #1-4584-4610'

" #2-4211-4220'

" #3-4175-4178'

TREATMENT: #1-(Acid)-4584-4610'

" #2- " -4211½-4220'

Schlumberger Log.

e-Wells correlation Log to 4643

NG FORMATIONS:

4175-4178'

BEST COPY
AVAILABLE