

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-1-34W

Company. SKELLY OIL COMPANY
Farm. F. E. Bartosovsky No. 6

SEC. 9 T. 1 R. 34W
C SE SW

Total Depth. 4351' PB 4312'
Comm. 5-1-60 Comp. 5-27-60
Shot or Treated.
Contractor. Claude Wentworth Drlg.
Issued. 4-1-61

County Rawlins
KANSAS



Elevation. 3131' DF

Production. 186 BOPD

CASING:

8 5/8" 367' cem w/300 sx.
5 1/2" 4351' cem w/200 sx.

Figures Indicate Bottom of Formations.

clay, sand & shale	372
shale & sand	2075
shale & pyrite	2550
shale	3468
lime & shale	4351
Total Depth	
Plugged back to 4312'	

TOPS:

Fort Hays	1488
Permian	2710
Stone Corral	2968
Admire	3652
Topeka	3824
Oread	3917
Lansing	4116
Marmaton	4323

Ran Schlumberger Induction-Electrical
Survey and MicroLog.

DST #1 4212-4222', op 1½ hrs, rec. 80'
clean oil, no water. IFP 15#, FFP 50#,
ISIP 945#/30 min, FSIP 930#/30 min.
IHP 2080#, FHP 2075#.