

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas


9-1-34W

Company- SKELLY OIL COMPANY  
 Farm- C. G. Kisling No. 2

SEC. 9 T. 1 R. 34W  
 C NE NE

Total Depth. 4286' PB 4242'  
 Comm. 4-23-60 Comp. 5-27-60  
 Shot or Treated.  
 Contractor. Claude Wentworth Drlg.  
 Issued. 4-1-61

County Rawlins  
 KANSAS



Elevation. 3076' DF

Production. 218 BOPD

CASING:

8 5/8" 371' cem w/300 sx.  
 5 1/2" 4285' cem w/250 sx.

Figures Indicate Bottom of Formations.

sand, clay & shale 375  
 sand & shale 2310  
 sand, shale & pyrite 2790  
 shale & lime 3720  
 lime 3950  
 lime & shale 4286  
 Total Depth  
 Plugged back to 4242'

TOPS:

Fort Hays 1442  
 Permian 2670  
 Stone Corral 2921  
 Admire 3602  
 Oread 3857  
 Topeka 3772  
 Lansing 3960  
 Macmaton 4260

Ran Schlumberger Induction-Electrical  
 Survey & MicroLog.

DST #1 4160-4174', op 1 hr, rec. 1842'  
 oil, 90' heavily oil cut mud, and no  
 water. IFP 120#, FFP 600#, ISIP 1075#,  
 FSIP 970#, Hydrostatic pressure 2150#.