

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
505 East Mardock, Wichita, Kansas


9-1-34W

Company- ALLAN, ET AL
Farm- Sis No. 4

SEC. 9 T. 1 R. 34W
SE NW NE

Total Depth. 4208'
Comm. 10-6-59 Comp. 11-10-59
Shot or Treated.
Contractor. Tom Allan
Issued. 1-9-60

County Rawlins
KANSAS



CASING:

8 5/8" 307' cem w/175 sx.
5 1/2" 4203' cem w/125 sx.

Elevation. 3083' RB

Production. 120 BOPD

All depths from RB.

Figures indicate Bottom of Formations.

sandy yellow clay	120	lime, show of oil	4138
lime & sand	210	red & green shale	4163
blue shale	307	lime, good porosity	
shale	1450	& saturation	4175
lime	1500	red shale	4201
sand & shale	1550	lime, oil stained	4204
shale	1850	CHANGE TO CABLE TOOLS	
sand & shale	2420	lime	4208 4 gal. Oil/hr.
green shale	2650	Total Depth	
red shale	2924	TOPS:	
red shale & shells	3500	Anhydrite	2924
sand	3505	Topeka	3773
lime	3514	Lansing	3968
red & gray shale	3558		
lime, Dk. stain	3563	Acid 250 gal. - 10 gal. Oil/hr.	
shale	3577	Ran Gamma Ray-Neutron Log	
lime	3581	Perforated 23 holes 4165-4169	
shale	3592	Swabbed 40 bbl. Oil/hr from 2800' deep.	
dolomite	3595		
lime	3604		
red shale	3634		
lime	3640		
red shale	3659		
lime	3663		
red shale	3680		
lime	3688		
red shale	3710		
lime	3715		
shale	3722		
lime	3726		
shale	3734		
lime & Pet. Residue	3740		
shale & shells	3773		
lime	3790		
shale	3804		
lime & Residue	3813		
shale	3842		
lime	3846		
shale	3850		
dolomite, Oil Stained	3855		
lime, free oil	3860		
lime	3896		
gray & black shale	3917		
brown lime	3922		
shale	3931		
sand	3940		
shale	3955		
red shale	3968		
lime, oil in bottom	3982		
shale	3985		
sand, Oil saturated	3992		
red shale	4018		
lime, good oil saturation	4029		
red shale	4042		
lime, show oil	4045		
red shale	4074		
lime	4080		
red & green shale	4118		
lime, light stain	4127		
red shale	4136		