

COMPANY REMARKS

**WRS COMPLETION REPORT**

SEC 3 TWP 1S RGE 34W PAGE 1

PI# 15-A-0029 CI-20-70

KANSAS RAWLINS 660 FSL 660 FWL C SW SW D DO  
STATE COUNTY FOOTAGE SPOT INIT. FIN.

SKELLY OIL 6 C G KISLING  
OPERATOR WELL NO. LEASE NAME

3121 KB 3116 GR CAHQJ  
OPER. ELEV. DISTRICT FIELD/POOL/AREA

11/26/1969 12/30/1969 ROTARY IDN 15-153- 20063  
SPUD DATE COMP. DATE TYPE TOOL PERMIT OR WELL I.D. NO.

4350 PENNSYLVY LEBEN OIL  
PROJ. DEPTH PROJ. FORM CONTRACTOR STATUS

4315 LANS-K C  
DRILLER'S T.D. LOG T.D. PLUS BACK T.D. OLD T.D. FORM. T.D.

CSG 8 5/8 @ 352 W/ 225 5 1/2 @ 4314 W/ 200 01 03

WELL IDENTIFICATION CHANGES

WHOS CODE # 15S001W03403181169

INITIAL POTENTIAL

IPP 202BOPD 298W 24HRS  
 LANS-K C PERF 4033- 4042 4067- 4070 4170- 4176 4208- 4220 GROSS 012  
 PERF 4252- 4262  
 ACID 4208- 4262  
 ACID 4170- 4176

TYPE	FORMATION	DEPTH	DATUM	FORMATION	DEPTH	DATUM
LOG	TOPEKA	3822		LANS-K C	4012	
	OREAD	3910				
SPL	STN CORL	2964				

FORMATION TEST DATA

DST 01 4022- 4176 LANS-K C S002  
 REC 930FT GAS 580FT OIL 300FT HM&GCO  
 REC 600FT O&GCM  
 INIT OP 0H30M GOOD BLOW  
 FINAL CP 2H IFP 396 FFP 703 BHT 122F  
 ISIP 1127 1H FSIP 1068 2H IHP 2177 FHP 2138

PRODUCTION TEST DATA

PTS 180CFO  
 LANS-K C PERF 4170- 4262 GROSS 004

Petroleum Information Corporation



-----  
 SKELLY OIL 6 C G KISLING  
 -----

PRODUCTION TEST DATA

PERF 4170- 4176 4208- 4220 4252- 4262

PTS CBO  
 LANS-K C PERF 4252- 4262 005  
 ACIDIZED, FAILED /NO AMT REPORTED/

PTS 72BO  
 LANS-K C PERF 4208- 4262 006  
 ACID 4208- 4262 400GALS  
 RATE 0.58/MIN MAX PRESS 400  
 MIN PRESS 200

PTS 56BO  
 LANS-K C PERF 4170- 4176 007  
 ACID 4170- 4176 200GALS  
 SWBD 16 BO

LANS-K C PERF W/ 3/FT 4033- 4070 GROSS 008  
 PERF 4033- 4042 4067- 4070

PTP 216BO 22HRS  
 LANS-K C PERF 4033- 4262 GROSS 009  
 PERF 4033- 4042 4067- 4070 4170- 4176 4208- 4220  
 PERF 4252- 4262

PTP 191BOPD 31BW 24HRS  
 LANS-K C PERF 4033- 4262 GROSS 010

PTP 186BOPD 21BW 24HRS  
 LANS-K C PERF 4033- 4262 GROSS 011

LOGS AND SURVEYS /INTERVAL,TYPE,COMPANY/

DILL SNP  
 MICL CCRL

DRILLING PROGRESS DETAILS

11/17 LOC  
 11/28 DRLG 1970  
 12/01 DRLG 3805  
 01/14 4315 DTD, PB 4048  
 COMP 12/30/69, IPP 202 BOPD, 29 BW, 24 HR  
 TEST  
 PROD ZONE - LANS-K C 4033-4262 /GROSS/  
 NO CORES, ONE DST