

COMPANY REMARKS

WRS COMPLETION REPORT
PI# 15-A-0015 11/20/70

SEC 10 TWP 1S RGE 34W
PAGE

KANS RAWLINS 660 FNL 1980 FEL

WELL CLASS
C NW NE WO DO

STATE COUNTY FOOTAGE
ASPEN RESOURCES LTD

SPOT
1 KEESLING

OPERATOR
3152 KB 3147 GR

WELL NO. LEASE NAME

CAHOJ

OPER. ELEV. DISTRICT

FIELD/POOL/AREA

IDN 15-153- 20084

COMMERCIAL ELEV.

LEASE NO.

PERMIT OR WELL I.D. NO.

SPUD DATE 10/06/1970 COMP. DATE 11/18/1970 ROTARY

OIL

TYPE TOOL
4350 KANSAS C ASPEN

PROJ. DEPTH PROJ. FORM. CONTRACTOR

DTD 4365 LTD 4365

FM/TD KANSAS C

DRILLER'S T.D. LOG T.D. PLUG BACK T.D. OLD T.D.

FORM./T.D.

CASING DATA

CSG 8 5/8 @ 363 W/ 250 5 1/2 @ 4364 W/ 300 01 09

WELL IDENTIFICATION CHANGES

WHCS CODE # 15S001W03410520970

INITIAL POTENTIAL

IPP 153BOPD 18BW
LANSING PERF W/ 2/FT 4048- 4240 GROSS 013
PERF 4048- 4052 4066- 4068 4084- 4086 4094- 4096
PERF 4110- 4129 4117- 4119 4149- 4152 4197- 4201
PERF 4215- 4217 4236- 4240
ACID 4117- 4119
ACID 4048- 4240
IPP 153 BOPD PLUS 12% WTR /18.36 BW/

TYPE	FORMATION	DEPTH	FORMATION	DEPTH	FORMATION	DEPTH
LOG	ANHYDRIT	2995	FT RILEY	3217	FORAKER	3633
LOG	WABAUNSE	3680	TOPEKA	3849	DEER CRK	3881
LOG	OREAD	3936	DOUGLAS	4006	LANSING	4043
LOG	BANHYDRIT	3030	BDOUGLAS	4024	BKANSAS C	4311
SPL	TOPEKA	3854	LANSING	4043		

FORMATION TEST DATA

DST 01 4045- 4058 LANSING
REC 5FT MUD

002

PI-WRS:RMS

Petroleum Information CORPORATION



©

ASPEN RESOURCES LTD

1 KESLING

FORMATION TEST DATA

FINAL OP OH45M IFP 20 FFP 20
ISIP 30 OH30M FSIP 23 OH23M

DST 02 4058- 4090 LANSING S003
REC 90FT OCM
FINAL OP 1H30M IFP 62 FFP 80
ISIP 1075 1H FSIP 672 1H

DST 03 4088- 4110 LANSING S004
REC 40FT MCO
FINAL OP 1H IFP 25 FFP 60
ISIP 1023 1H FSIP 1010 1H

DST 04 4105- 4170 LANSING S005
REC 730FT GAS 115FT OIL 60FT HOCH
FINAL OP 1H IFP 70 FFP 150
ISIP 1275 1H FSIP 1170 1H

DST 05 4160- 4210 LANSING S006
REC 240FT GAS 1220FT G&MCO 90FT M&OCW
FINAL OP 1H IFP 170 FFP 550
ISIP 1255 OH45M FSIP 1250 OH45M

DST 06 4210- 4230 LANSING S007
REC 100FT OIL 20FT MCO
FINAL OP 1H IFP 40 FFP 105
ISIP 595 OH45M FSIP 585 OH45M

DST 07 4233- 4255 LANSING S008
REC 1100FT GAS 720FT OIL 180FT MCO
FINAL OP 1H IFP 85 FFP 455
ISIP 565 OH45M FSIP 560 OH45M

PRODUCTION TEST DATA

PTS 2180 10BW 2HRS
LANSING PERF W/ 2/FT 4048- 4240 GROSS 010
PERF 4048- 4052 4066- 4068 4084- 4086 4149- 4152
PERF 4197- 4201 4215- 4217 4236- 4240

PTS 1080 18BW
LANSING PERF W/ 2/FT 4117- 4119 011
ACID 4117- 4119 500GALS

PTS 1480PH 1HRS
LANSING PERF W/ 2/FT 4048- 4240 GROSS 012
PERF 4048- 4052 4066- 4068 4084- 4086 4094- 4096

PI# 15-A-0015 11/20/70

SEC 10 TWP 1S RGE 34W
PAGE

ASPEN RESOURCES LTD

1 KEESLING

PRODUCTION TEST DATA

PERF 4110- 4129 4117- 4119 4149- 4152 4197- 4201
PERF 4215- 4217 4236- 4240
ACID 4048- 4240 4000GALS

DRILLING PROGRESS DETAILS

09/16 LOC
10/05 MIRT
10/07 DRLG 1100
10/08 DRLG 2495
10/12 4090 TD, RNG DST #2
10/13 DRLG 4125
10/14 4160 TD, RNG DST #5 4110-4160
10/16 DRLG 4260
10/19 4365 TD, RNG 5 1/2 CSG
10/28 4365 TD, TSTG
11/09 4365 TD, POP
11/18 4365 TD
COMP 11/18/70, IPP 153 BOPD, PLUS 12% WTR
PROD ZONE - LANSING 4048-4240 /GROSS/
NO CORES, SEVEN DSTS