

12-1-35W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- EMPIRE DRILLING COMPANY
Farm- Sis No. 1

SEC. 12 T. 1 R. 35W
C SW SW

Total Depth. 4320'
Comm. 8-18-62 Comp. 8-31-62
Sect or Treated.
Contractor.
Issued. 11-17-62

County RAWLINS
KANSAS



Elevation. 3113' KB

Production. 190 BOPD, NW

CASING:

8 5/8" 213' cem w/100 sx.
5 1/2" 4312' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface hole	221
shale	2409
gypsum	2425
sand, stone & shale	2622
sand-shale	2700
shale	2801
gyp	2815
shale	2982
anhydrite	3021
shale & shells	3125
shale	3205
lime	3245
shale	3340
lime & shale	3655
lime	3710
lime & shale	3963
lime	4009
lime & shale	4040
lime	4050
lime & shale	4105
lime	4115
lime & shale	4180
lime	4215
shale & lime	4245
lime	4250
lime & shale	4310
lime	4320 RTD
Total Depth	

TOPS: SCHLUMBERGER LOG

Anhydrite (Scout)	2982
Admire Group	3652
Topeka	3819
Deer Creek	3862
Oread	3908
Leavenworth	3988
Douglas Sand	4004
Lansing Kansas City	4036
Base Kansas City	4305