

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


13-1-35W

Company- BURCH EXPLORATION, LTD & JACK MORRIS
Farm- Chadderdon No. 2

SEC. 13 T. 1 R. 35W
C NE NW

Total Depth. 4692'
Comm. 2-26-63 Comp. 3-16-63
Shot or Treated.
Contractor.
Issued. 8-10-63

County Rawlins
KANSAS



CASING:

8 5/8" 265' cem w/225 sx.
5 1/2" 4691' cem w/350 sx.

Elevation. 3116' KB

Production. 79 BOPD

Figures indicate Bottom of Formations.

shale	2295
shale & lime	2701
shale	2798
Anhydrite	2811
shale	2820
shale & lime	2981
Anhydrite	3019
lime & shale	3948
lime & chert	3965
lime-sand-shale	4041
lime & shale	4200
lime	4250
lime & shale	4500
lime	4603
lime & shale	4663
lime	4671
lime & shale	4692 RTD
Total Depth	

TOPS: LOG

Topeka	3822
Deer Creek	3864
Oread	3904
Douglass	3990
Lansing	4038
Base Kansas City	4304
Marmaton	4339
Cherokee	4521
Mississippi	4685

DST #1 4120-50' Op 2 hrs. Rec. 1380'
gas, 1080 clean oil, 180' slightly
muddy oil. IBHP 618#/30 min., IFP
108#, FFP 375#, FBHP 559#/30 min.

DST #2 4170-4200' op 2 hrs. Rec.
420' slightly oil cut wtr.; 45' slightly
oil cut watery mud. IBHP 1206#/30 min.
IFP 0, FFP 158#, FBHP 1135#/30 min.

DST #3 4223-50' Op 2 hrs. Rec. 295'
clean oil, 60' muddy oil, 120' watery
oil, 240' oil cut slat wtr. IBHP 254#/
30 min., IFP 130#, FFP 208#, FBHP 254#.