

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


14-1-35W

Company- SKELLY OIL COMPANY
Farm- Savage No. 1

SEC. 14 T. 1 R. 35W
C NE NE

Total Depth. 4370'
Comm. 7-5-62 Comp. 7-14-62
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 10-20-62

County Rawlins
KANSAS



Elevation. 3157' KB

Production. 43.47 BO & 64 BSWPD

CASING:
8 5/8" 287' cem w/250 sx.
5 1/2" 4370' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface clay	85
clay - sand	215
shale	1160
sand - shale	1540
shale	1990
shale & sand	2240
shale - sand - pyrite	2390
hard sand - shale	2515
shale - sand	2735
GYP	2765
shale - red bed - gyp	2955
red bed	3027
anhydrite	3060
shale	3065
shale & sand	3250
lime - shale	4210
lime	4275
lime & shale	4370 RTD
Total Depth	

TOPS: ELECTRIC

Anhydrite	3027
Lansing/Kansas City	4079
Lansing "G"	4180
Lansing "H"	4231
Base/Kansas City	4344

DST #1 4177-4210' op 1½ hrs. Rec. 120'
free oil, 60' cut mud, 60' water & oil cut
mud, 240' muddy salt water w/show of oil.
IF 45# FF 210# IBHP 1065#/30 min.
FBHP 1035#/30 min.