

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

30-20-10W


Company- D. R. LAUCK OIL COMPANY, INC.
Farm- Yeo No. 1

SEC. 30 T. 20 R. 10W
C N/2 N/2 NE

Total Depth. 3400'
Comm. 6-16-62 Comp. 6-24-62
Shot or Treated.
Contractor.
Issued. 12-8-62

County Rice

KANSAS



CASING:
8 5/8" 201' cem w/180 sx.

Elevation. 1737' DF

Production. DRY

Figures Indicate Bottom of Formations.

sand	60
shale	201
red bed	416
anhydrite	430
lime	440
shale & shells	1200
shale & lime	1385
anhydrite & shells	1465
lime, shale & shells	1640
lime & shale	1840
lime	1940
shale & lime	2320
broken lime & shale	2525
lime & shale	2580
lime	2670
lime & shale	2755
lime	2841
Heebner	2845
lime & shale	2895
shale & lime	3010
lime	3265
shale	3294
Arbuckle lime	3400 RTD
Total Depth	

TOPS: SAMPLE

Heebner	2841
Toronto	2858
Douglas	2875
Brown Lime	2970
Lansing	2990
Simpson	3273
Arbuckle	3294

DST #1 (S) 3041-3085' Op 1 hr. w/fair
blow thruout. Rec. 120' gas, 65' slightly
oil & gas cut mud. ISIP 10#/20 min.
FSIP 8#/30 min. IFP 3#. FFP 7#.

DST #2 (S) 3290-3300' Op 1 hr. w/fair
blow thruout. Rec. 150' clean oil, 115'
watery oil (50% water), 20' water.
ISIP 1058#/30 min. FSIP 1010#/30 min.