


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.
 W. M. Panning No. 14-B.

SEC. 10 T. 20 R. 11W
 NE SW SE
 990' N SL 990' E WL

Total Depth. 3283'
 Comm. 12-30-38 Comp. 1-10-39
 Shot or Treated. No.
 Contractor.
 Issued. 3-18-39 Rotary 3283

County. Barton



CASING:
 10 3/4" 283'
 7" 3276'

Elevation.

Production. Pot. 2244 B.
 Figures Indicate Bottom of Formations. No water

sand, shale & red rock	495
anhydrite	520
shale & shells	1015
salt	1200
shale & shells	1335
lime brkn	1540
shale & shells	1692
lime brkn	1868
shale & shells	2575
lime	3010
lime & shale	3065
lime	3165
lime hrd	3180
lime sft	3209
lime	3272
Rotary Coring Record	
Core #1 3'/11' recovery	
grey shale w/lime strks	3275
dolomite, no show	3277
dolomite, fair porosity, spotted saturation	3279
dolomite sft, fair porosity, good show oil	3283
Total Depth.	

Top Lansing Lime 3035

Arbuckle Dolomite 3275-83

Swabbed 100 B.Oil, no wtr, per hr
 thru 7" casing, natural - 1 hr
 test.
 State Potential 2244 B.Oil, no
 water, pumping.