

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


STANOLIND OIL & GAS CO.  
Wm. Panning No. 16-B.

SEC. 10 T. 20 R. 11W  
SW NE SE  
1650' N SL 1650' E WL

Total Depth. 3367'  
Comm. 5-13-39 Comp. 5-31-39  
Shot or Treated.  
Contractor.  
Issued. 8-26-39

County. Barton

CASING : Rotary 3367  
8 5/8" Attempted completion  
5 1/2" w/cable in Lansing only.  
219'4"  
3195'



Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	80
shale, sand & shells	165
shale, shells & red bed	489
red bed	495
anhydrite	520
red rock & shale	900
shale & lime shells	977
shale & salt	1235
shale & shells	1300
shale & brkn lime	1340
lime	1385
lime & gyp	1485
lime	1758
shale & shells	1798
shale & lime	2665
lime	2948
shale & lime	3040
lime	3080
red rock & shale	3090
lime brkn	3137
lime	3160
lime brkn	3168
lime	3200
lime oolitic very porous	
w/fair sh lgt, live oil	3215
lime	3270
shale gy	3272
lime	3284
shale & lime, conglomerate	3352
shale red & green	3355
dolomite tan, sulphur odor	3367
Total Depth.	

Top Lansing 3040  
Base Lansing 3284  
Arbuckle dolomite 3355-67

Completed as dry hole in both  
Arbuckle & Lansing-Maximum  
production was  $\frac{1}{2}$  BO & 6 BWPB  
on 12-hr test in Lansing.