


19-20-11W

HOLLOW DRLG.CO., INC.
Andreae No. 1.

SEC. 19 T. 20 R. 11W
CW $\frac{1}{2}$ NW NW

Total Depth. 3310 $\frac{1}{2}$ '
Comm. 4-29-39 Comp. 5-24-39
Shot or Treated. 5-24-39 2000 Gals.
Contractor. Hollow Drlg.Co., Inc.
Issued. 6-24-39 Rotary w/cable
tool completion

County. Barton



Elevation.

CASING:
8 5/8" 240'
5 1/2" 3294'

Production. Pot. 3262 B.

Figures Indicate Bottom of Formations.

sand	40
shells & sand	180
shale	190
sand	195
shale	205
shale & sand	250
red rock	540
anhydrite lime	570
shale & shells	1025
salt & shells	1200
shale & shells	1362
lime & shale	1466
shale & shells	1480
lime	1525
shale	1550
shale & shells	1600
lime	1620
shale	1625
lime	1645
shale	1650
lime & shale	1688
lime	1705
shale	1735
lime hrd	1753
lime	1770
pyrite of iron	1772
lime	1795
shale & shells	1820
lime	1859
lime & shale	1937
shale & shells	1990
lime brkn	2035
lime	2070
shale & shells	2100
lime	2175
shale & shells	2250
lime & shale	2342
shale	2370
lime	2385
lime brkn	2435
lime	2475
shale	2480
lime	2482
lime & shale brks	2500
shale blue	2525
lime brkn	2531
shale & lime	2590
shale & shells	2677
lime Topeka	2716
lime	2910
lime brkn	2920
lime	2979
lime & shale	3022
shale & shells	3050
shale & lime	3080
lime K.C.	3294
sh oil 3115-3120	
lime Arbuckle oil	3310 $\frac{1}{2}$
Total Depth.	