

Plot of D. M. 1917
19-20-11W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

HOLLOW DRILLING CO., INC.
Andreae No. 3.

SEC. 19 T. 20 R. 11W.
CE 1/2 NW NW

Total Depth. 3343
Comm. 2-28-41 Comp. 3-16-41
Shot or Treated.
Contractor. Hollow Drilling Co., Inc.,
Issued. 4-19-41.

County Barton.

CASING. Rotary Drilling Tools.
Completed with Cable tools.

8 5/8" 255' cemented.
5 1/2" 3303' 4" cemented.

Elevation.

Production. Min. Well.

Figures Indicate Bottom of Formations.

Cellar	9
sand	120
shale	130
sand	150
shale	190
sand	210
shale	220
red bed	245
red rock	540
anhydrite lime	560
shale and shells	920
shale and shells salt	1340
shale and lime	1800
lime	1875
shale and shells	2010
shale and lime	2170
shale	2293
shale lime shells	2415
lime and shale	2480
shale and shells	2585
lime shale breaks	2672
lime	2970
shale	3064
lime	3137
lime	3306
3306 equals 3304 T.D. Derrick	
floor 3303' Top Arbuckle Derrick Floor.	
Arbuckle lime	3345

Total Depth.

Hole filled 100' with oil 3303-09
Acidized with 1000 gal at 3322. Swabbed 3.58 bbls hr. no wtr
Swabbed 7.61 bbls per hr at 3343 before acidizing.
acidized with 1000 gal, swabbed 8.27 bbls per hr at 3343.

