

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


19-20-11W

HOLLOW DRILLING CO. INC.
P. Scheufler No. 1.

SEC 19 T. 20 R. 11 W.
NEc NE

Total Depth. 3344
Comm. 12-28-41 Comp. 1-17-42
Shot or treated
Contractor. Hollow Drilling Co., Inc.
Issued. 3-7-42

County Barton.



CASING. Rotary Drilling tools.
Completed with Cable tools.

8 1/4" 242' cemented.
5 7/8" 3310 1/2' cemented.

Elevation.
Temporary
Production. Pot. 56 B.

Figures Indicate Bottom of Formations.

cellar	11
sand and gravel	145
shale blue	200
sand	228
shale and lime shells	242
red rock & shells	523
anhydrite lime	558
red rock & shells	795
shale	1050
red rock and salt	1206
salt	1300
lime and shale	1440
lime and shale breaks	1655
lime and shale	1725
limo	1834
lime and shale	2110
shale	2192
lime and shale	2295
shale and limo	2532
shale	2580
limo	2610
shale	2680
Topoka limo	2688
limo	2911
shale and limo	2976
limo	3015
shale	3046
shale and limo	3093
limo	3314
3314 equals 3311 1/2 DF corr.	
Arbuckle slight show	
oil	3316 1/2
Arbuckle	3319 1/2
Arbuckle hard	3324
Arbuckle limo	3344
Total Depth.	

Acidized with 3000 bbls acid
Swabbed 50 bbls in 5 hours from
bottom st 3344

Top of Arbuckle 3310 D.F.

Potential Test 1-17-42
56 bbls. Tomporary Swab Test.