

19-20-11 W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

HOLLOW DRILLING CO., INC.  
P. Scheufler No. 2

SEC. 19 T. 20 R. 11 W.  
NE NW NE

Total Depth. 3324  
Comm. 2-15-42 Comp. 3-6-42  
Shot or Treated.  
Contractor Hollow Drilling Co., Inc.  
Issued. 4-25-42 Rotary and Cable.

County Barton.



CASING.

8 1/2" 235' cemented.  
5 1/2" 3305' cemented.

Elevation.

Temporary  
Production. Pot. Swab 50B.

Figures Indicate Bottom of Formations.

cellar	10
sand	145
shale and shells	190
sand	215
shale and shells	236
shale	510
anhydrite lime	540
shale	720
shale and shells	1050
salt	1327
shale and lime	
shells	1475
lime	1580
lime and shale	1605
sand	1625
shale and shells	1775
lime	1830
shale and shells	1870
shale and lime	
shells	2000
shale and shells	2045
lime	2080
shale and lime	
shells	2200
lime and shale	2350
shale & lime shell	2450
shale and lime	2520
shale & lime shell	2645
shale and lime	2670
Topeka lime	2715
lime	2890
shale	2940
lime	2998
shale	3075
lime	3308
Arbuckle lime	3324

Top of Arbuckle lime 3306.  
Top of Arbuckle Derrick Floor Correction 3304

Potential Test 3-6-42  
50 bbls. Temporary Swab test.

REMARKS- cored from 3306-3311  
Treated well with 4000 gal acid  
Hole filled 300' with oil in 10 1/2 hrs.

Total Depth.