

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


19-20-11W

COMPANY MERRY "A" DRLG. INC & OSCAR STUTENROTH
 FARM Scheufler NO. 1

SEC. 19 T. 20 R. 11W
 LOC. SW SW NE

TOTAL DEPTH 3379' RTD
 COMM. 7-19-65 COMP. 7-25-65
 SHOT OR TREATED
 CONTRACTOR Merry "A" Drlg. Inc.
 ISSUED 12-9-67

COUNTY Barton



CABING

20	10
15	8 5/8
12	6
13	5

ELEVATION 1804 KB
 PRODUCTION DRY

FIGURES INDICATE BOTTOM OF FORMATIONS

Limestone. No shows oil 2975-2980
 Limestone. fair oocastic porosity. No free oil, no odor. 3104-3108
 Limestone: scattered stain, weak show of free oil. 3119-3122
 Limestone: No free oil and no odor. 3140-3142
 Limestone: Spotty dead stain. No free oil and no odor in fresh samples. 3158-3160
 Limestone: Spotty light brown stain No free oil and no odor in fresh samples 3182-3184
 Limestone: scattered dead staining. No free oil & no odor. in fresh samples 3192-3204
 Limestone: No shows of oil 3232-3235
 Limestone: Dull spotty dead stain. No free oil & no Odor in fresh samples 3262-3266
 Limestone: No free oil & no odor in fresh samples. 3278-3281
 Limestone: No free oil & strong odor in fresh samples 3316-3322
 Shale gray to green waxey sand: Weak show of free oil & weak odor in fresh samples 3358-3362
 Dolomite: Spotted brown to dark black stain. No free oil, weak odor in fresh samples. 3364-3379
 Rotary Total Depth

DST #1 3310-3329
 Open: 25 Min.
 Blow: Weak for 4 min.
 Pressures: All Pressures zero.
 DST #2 3344-3371
 MIS-RUN.

TOPS:	ELECTRIC
Anhydrite (drillers)	555
Heebner	2958
Toronto	2973
Douglas	2987
Brown Lime	3085
Lansing	3101
B/Kansas City	3323
Simpson	3350
Simpson sand	3358
Arbuckle	3364