

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

26-20-11W

Company. CITIES SERVICE OIL CO.
Farm- R. Bryant "B" No. 3

SEC. 26 T. 20 R. 11W
NW NE NW
330' S & 990' W of N/4c

Total Depth. 3294
Comm. 4-24-53 Comp. 5-8-53
Shot or Treated.
Contractor. Barbour Drilling Co.
Issued. 7-18-53

County Barton
KANSAS

CASING:

8 5/8 set at 214' w/ 150 sx cement
5 1/2 set at 3270' w/ 125 sx cement

Elevation. 1759

Production. Pot. 17 BO, 2 BW

Figures indicate Bottom of Formations.

sand & clay	80
shale	145
red bed & shells	335
red bed	465
anhydrite	485
shale & shells	1285
anhydrite	1380
shale & anhydrite	1415
lime & shale	1900
shale	2375
lime & shale	2750
lime	2832
lime & shale	3090
lime	3167
lime & shale	3253
lime	3294
Total Depth	

TOPS:

Heebner	2873
Dodge	2894
Douglas sand	2935
Brown lime	3000
Lansing	3017
Arbuckle	3267
Penetration	27

98 gals oil in 4 hrs. 20 min.

5-8, Acidized 1000 gals.
5-11, pumped 14 oil, no water, 24 hrs.
5-13, Acidized 1000 gals. Jel acid
& 2000 gals regular
5-18, pumped 10 oil 4 water 24 hrs.

3270 RTD=3270 SLM