

*G. E. Jamison*  
 26-20-11W


IND. TERR. ILL. OIL CO.  
 L. Schropel No. 2A.

SEC. 26 T. 20 R. 11W  
 NE SE NE  
 990' fr SL 440' fr EL NE  $\frac{1}{4}$

NOV 6 1937

Total Depth. 3298  $\frac{1}{2}$ '  
 Comm. 7-25-37 Comp. 8-14-37  
 Shot or Treated. 2000 Gals. 8-16-37  
 Contractor. Arrow Drlg. Co.  
 Issued. 11-6-37 Rotary & Cable.

County. Barton



Elevation.

CASING:  
 10  $\frac{3}{4}$ " 203'  
 7 " 3275'7"

Production. Pot. 497 B. 8 hr.

Figures Indicate Bottom of Formations.

surface sand	203
shale & shells	868
shale, shells, salt	1230
shale & shells	1464
salt	1494
lime & shale	1534
brkn lime & shale	1674
sand hrd	1710
shale	1785
shale & shells	1930
lime & shale	2070
brkn lime & shale	2200
shale & shells	2342
brkn limo & shale	2545
lime & shale	2662
lime	2780
shale	2800
lime	2920
brkn lime & shale	3000
lime	3280
Siliceous lime	3282
sdv lime	3298 $\frac{1}{2}$
Total Depth.	