

GULF OIL CORPORATION.
Mary Meyer No. 3

SEC. 13 T. 20 R. 11W.
CW $\frac{1}{2}$ SE SE

Total Depth. 3256 $\frac{1}{2}$
Comm. 3-28-41 Comp. 4-18-41
Shot or Treated. 2000 gal. 4-18-41
Contractor.
Issued. 6-28-41

County Barton.



CASING.

85/8" 168' Cem.
5 $\frac{1}{2}$ " 3252' Cem.

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. No water, sonic meter.

sand and gravel	55
shale blue	135
shale	170
red bed	320
shale red	439
red and grey shale and gyp shells	552
shale blue and shells	895
shale and shells	975
salt	1175
lime and shale	1240
anhydrite and shale brks	1395
anhydrite, lime and shale	1600
anhydrite lime and shale	1700
anhydrite and shale breaks	1810
lime and shale breaks	1925
lime and shale breaks	2025
shale blue and lime	2075
lime	2090
shale blue and lime shells	2112
shale blue and lime	2240
lime and shale	2350
shale blue and lime	2433
shale blue and lime shells	2585
lime	2605
shale dark	2620
lime	2706
lime and shale	2743
lime and shale breaks	2788
lime and shale	2848
lime	2898
lime and shale streaks	2980
lime and shale	3047
lime with small shale breaks	3110
limo	3140
lime and shale	3210
lime and congl.	3251
dolomite	3253
Arbuckle	3256 $\frac{1}{2}$

Total Depth.

Arbuckle lime 3251-3256 $\frac{1}{2}$