


IND. TERR. ILL. OIL CO.
Will Peters No. 1.

SEC. 13 T. 20 R. 11W
NWc NW
340' fr WL 330' fr NL NW $\frac{1}{4}$

Total Depth. 3290'
Comm. 10-24-38 Comp. 11-11-38
Shot or Treated. 2000 & 4000 Gals.
Contractor. Glenn Drlg. Co.
Issued. 2-4-39 Rotary & Cable

County. Barton



Elevation.

CASING:
10 $\frac{3}{4}$ " 172'
7" 3272'

Production. Pot. 203 Bbls.

Figures Indicate Bottom of Formations.

cellar	7	Kansas City lime grey med hrd	3095
surface sand white sft	50	Kansas City lime wh sft	3101
clay yellow sft	70	lime grey hrd	3119
brkn sand shells grey sft		lime wh med hrd	3161
& blue shale	145	brkn lime grey med hrd &	
red rock red sft	155	shale blue hrd	3188
red bed	250	lime porous grey drk sft	3192
red bed red sft	460	lime porous brown sft	3195
lime wh med	475	lime grey hrd	3220
red bed & blue shale	550	samples circulated at 3192, some	
shale blue & shells	610	oil show	
shale & shells blue sft	880	Halliburton line corr. 3212-3216	
shale blue sft	963	lime grey hrd	3271
salt & shale wh & grey sft	1094	Hole corrected to D.F. 3271-3268	
salt white sft	1250	lime grey hrd	3272
shale & shells blue & wh sft	1310	lime Siliceous brown sft	3274
shale blue sft	1350	dolomite lgt hrd	3275
brkn lime grey med	1395	show oil after drilling plug	
shale & lime strks blue &		no fillup	
grey med & hrd	1535	dolomitic lime lgt hrd	3277
brkn lime & shale grey &		dolomitic lime lgt med	3279
blue med hrd	1635	show of oil	
sdv lime grey sft	1668	dolomitic lime lgt sft	3290
lime grey hrd	1675	Total Depth.	
lime grey med hrd	1703		
shale & lime strks blue med	1748	Streaks porosity & staining 3279-99	
lime grey med	1765	Increase oil filled up 350' 4 $\frac{1}{2}$ hrs	
shale grey sft	1779	Swab 2 $\frac{3}{4}$ BO 6 hrs 11-12-38	
shale grey med	1790	HSLM 3290 TD	
shale blue med	1803	Swab 39.65 B. 23 hrs. 10-13-38	
shale & lime shells blue &		Acidized 2000 Gals. 11-15-38	
white med	1835	Acidized 4000 Gals. 11-27-38	
lime wh med	1856		
brkn lime blue & wh med	1883		
shale & shells blue & wh sft	1953		
lime brkn grey med	1975		
shale & lime strks	2034		
shale & lime strks grey med	2130		
brkn lime & shale grey &			
blue med	2214		
shale & shells blue sft	2284		
brkn lime blue & wh med	2298		
shale blue sft	2350		
brkn lime blue wh med	2450		
brkn lime & shale wh &			
blue med	2483		
shale blue med	2503		
lime grey hrd	2506		
brkn lime blue & grey med	2533		
lime grey med & hrd	2558		
lime grey med	2608		
lime grey med hrd	2629		
lime grey hrd	2779		
shale blue med	2785		
lime wh hrd	2864		
lime grey hrd	2934		
shale blue med	2969		
lime wh hrd	2998		
shale & lime blue med	3037		
brkn lime blue & grey med	3059		
lime(K.C.) grey med hrd	3086		