


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

GULF OIL CORP.
Henry Zahorsky No. 7.

SEC.14 T.20 R. 11W
CW $\frac{1}{2}$ SE SE

Total Depth. 3355' PB 3318'
Comm. 8-23-40 Comp. 9-27-40
Shot or Treated. 9-14-40 1000 Gals.
Contractor.
Issued. 12-7-40

County. Barton



CASING:
8 5/8" 143'
5 1/2" 3355'

Elevation.

Production. Pot. 2820 B. Sonic

Figures Indicate Bottom of Formations. Meter, 180 BW

| | |
|-----------------------------------|--------------------|
| sand | 100 |
| shale blue | 150 |
| red bed & shells | 670 |
| shale & shells | 975 |
| salt & shells | 1255 |
| anhydrite, lime & shale breaks | 1355 |
| anhydrite & lime | 1505 |
| lime | 1525 |
| shale & shells | 1535 |
| lime & shale brks | 1640 |
| lime & anhydrite w/ shale brks | 1705 |
| lime & shale brks | 1790 |
| lime & shale strks | 1855 |
| lime & shale brks | 1900 |
| lime & shale | 2138 |
| shale | 2169 |
| shale & lime | 2230 |
| shale & lime shells | 2380 |
| lime & small shale brks | 2405 |
| lime w/shale strks | 2445 |
| shale & shells | 2462 |
| shale blue & lime shells | 2522 |
| lime | 2548 |
| shale & shells | 2595 |
| lime | 2887 |
| lime w/shale strks | 2932 |
| lime & shale strks | 2981 |
| shale | 2990 |
| lime brkn & shale | 3016 |
| lime brkn & shale blue | 3076 |
| lime & shale blue | 3125 |
| lime & shale brks | 3172 |
| lime & shale | 3190 |
| lime | 3264 $\frac{1}{2}$ |
| cored | 3274 |
| lime | 3338 |
| lime cherty | 3355 |
| Total Depth. | |

Plugged back to 3318

Arbuckle lime 3264-3355

Perforated with five shots
from 3309 to 3311